

ADDENDUM NUMBER: 2

Addendum Issue Date: **August 23, 2021**

Project Title: **City of Edgerton, Kansas, 7th & Nelson Sanitary Sewer Rehabilitation**

This addendum adds, deletes, changes or clarifies the following:

ADDENDA TO PLANS AND PROJECT MANUAL:

1. Section 03360 Sewer Manhole Rehabilitation – Replace Part 3, 3.3 MANHOLE REHABILITATION, D) Cementitious Wall Rehabilitation, 5. Application, c. Spraying, (i) with the following:
“(i) On all manholes, a double application of the liner mix shall be spray applied to a total thickness of 1 inch two applications.”
2. Section 02538 Thermoformed Pipe Method (Fold and Form) – Replace Part 1, 1.7 Qualifications A) 1. with the following:
“1. Installer must have been in the Thermoformed (fold and formed) pipe rehabilitation business for at least two (2) years. In addition, the Installer must have successfully installed at least 100,000 feet the product in wastewater collection systems. The Installer’s onsite superintendents designated for this project must have had at least two (2) years of continuous active experience in the installation of pipe liners and have been employed by the installer for no less than the past twelve (12) months. Acceptable documentation of these minimum installation must be submitted to the Owner and/or Engineer.”
3. Clarifications on questions:
 - a. Q: Which manhole ring & cover does the City use?
A: Refer to APWA standard drawing MH-1, showing Ring & Cover to be Neenah R-1736, Clay & Bailey #2008, Deeter #1316, or approved equal.
 - b. Q: Is inspection information available to bidders?
A: Manhole inspection and CCTV inspection reports are available to bidders upon request.

NOTE: Bidders must acknowledge receipt of this Addendum by listing the addendum number and date, where provided, on the Bid Form.